

Draft FPP Change Form

9/14/07

Change Request Number: 08TDA_006

Date: 1/31/2008

Proposed by: USACE Fisheries

Location of Change

TDA section 6

Proposed Change:

Change to read as follows:

7. Forebay Debris Removal.

7.1. Debris at projects can impact fish passage conditions. It can plug or block trashracks, gatewell orifices, dewatering screens, separators, and facility piping resulting in impingement, injuries, and descaling of fish. The preferred option is to remove debris at each project when possible to avoid passing a debris problem on to the next project downstream. This is not always possible at each project as some projects do not have forebay debris removal capability. In this case, the only viable alternative is to spill to pass the debris.

7.2. Special spill operations that don't follow the normal spill schedule or volume limits will be coordinated prior to their execution. Normally, the project shall contact CENWP-OD at least two workdays prior to the day the special operation is required. Using information provided by the project, CENWP-OD will coordinate with FPOM and with RCC, as necessary. Once the coordination is complete, RCC will issue a teletype detailing the special operations.

Reason for Change:

Corrects labeling error and provides wording consistent with other NWP projects.

Comments from others:

Record of Final Action:

Language changed as proposed.